



NOTES:

1. ANNULAR SPACES BETWEEN THE CARRIER PIPE AND THE CASING PIPE SHALL BE EITHER FILLED WITH SAND OR GROUT IN ACCORDANCE WITH THE CONDITIONS OF THE PERMIT OR SPECIFICATIONS.
2. THE CASING SHALL HAVE WELDED JOINTS.
3. ENDS OF THE CASING PIPE SHALL BE BULKHEADED WITH BRICK AND MORTAR.
4. THE PIPE SHALL BE INSULATED FROM THE CASING AND SUPPORTED ON ALL SIDES BY THE USE OF WOODEN SKIDS. (SEE PIPE CASING DETAIL).
5. DISTANCE "A" FROM ROADWAY TO PIT TO BE DESIGNATED BY AUTHORITY GOVERNING THE ROADWAY.

REVISED 10-08-03 CADD DRAWING BY GTS CONSULTANTS, INC.

DATE: JAN. 1991

DRAWN: G.G.&J.T.R.

SCALE: NONE

LAKWOOD TOWNSHIP
MUNICIPAL UTILITIES AUTHORITY

BORE
CONSTRUCTION