

- NOTES:
- 1. INTERIOR SURFACES TO BE COATED WITH TWO COATS, 18 MIL TOTAL, COAL TAR EPOXY MEETING SPECIFICATION C-200(A) OR SSPC-PAINT 16 IF RECEIVING DIRECT DISCHARGE FROM PUMP STATION OR DIFFERENCE IN INVERT ELEVATIONS EXCEEDS 12".
- 2. RISER, CONES AND SLABS SHALL BE CONSTRUCTED IN ACCORDANCE WITH A.S.T.M. C-478.
- 3. NON PENETRATING LIFTING HOLES SHALL BE PROVIDED IN ALL UNITS.
- 4. ABSORPTION NOT TO EXCEED 8% IN ACCORDANCE WITH A.S.T.M. C-76.
- 5. ALL JOINTS TO BE CONSTRUCTED IN ACCORDANCE WITH A.S.T.M. C-361.
- 6. NO PRE-CAST BENCHES OR CHANNELS

PEVISED 7_14_11 | PEV EXTERIOR COATING & ADDED NOTE 7

7. CAN ONLY BE USED AT DEPTHS GREATER THAN 6.5' AS MEASURED FROM RIM TO INVERT.

DATE: JAN. 1991	CADD DRAWING BY GTS CONSULTANTS, INC. LAKEWOOD TOWN	ISHIP CONF. TO		40
DRAWN: G.G.&J.T.R. SCALE: NONE	MUNICIPAL UTILITIES A	UTHORITY CONE IC	OP MANHOLE	19