



NOTES:

1. INTERIOR SURFACES TO BE COATED WITH TWO COATS, 18 MIL TOTAL, COAL TAR EPOXY MEETING SPECIFICATION C-200(A) OR SSPC-PAINT 16 IF RECEIVING DIRECT DISCHARGE FROM PUMP STATION OR DIFFERENCE IN INVERT ELEVATIONS EXCEEDS 12".
2. RISER, CONES AND SLABS SHALL BE CONSTRUCTED IN ACCORDANCE WITH A.S.T.M. C-478.
3. NON PENETRATING LIFTING HOLES SHALL BE PROVIDED IN ALL UNITS.
4. ABSORPTION NOT TO EXCEED 8% IN ACCORDANCE WITH A.S.T.M. C-76.
5. ALL JOINTS TO BE CONSTRUCTED IN ACCORDANCE WITH A.S.T.M. C-361.
6. NO PRE-CAST BENCHES OR CHANNELS

DATE: JULY, 2011
 DRAWN: SGM OF GTS
 SCALE: NONE

**LAKEWOOD TOWNSHIP
 MUNICIPAL UTILITIES AUTHORITY**

WIDE MANHOLE DETAIL

37