

- PLACEMENT OF CURB STOP AND BOX SHOULD BE BETWEEN CURB AND SIDEWALK WHEREVER POSSIBLE. FOR INTEGRAL CURB AND SIDEWALK, PLACE CURB BOX BEHIND WALK.
- 2. OWNERS RESPONSIBILITY SHALL BE UP TO AND INCLUDING THE TUBE NUT WHICH THREADS ONTO THE CURB STOP.
- 3. THE AUTHORITY'S RESPONSIBILITY SHALL BE THE WATER MAIN, THE SERVICE LINE TO AND INCLUDING THE CURB STOP, AND WHERE APPLICABLE, THE DOUBLE STRAP TAPPING SADDLE.

 MAINTENANCE OF THE CONNECTION OF THE SERVICE LINE TO THE CORPORATION STOP TO THE BUILDING SHALL BE THE RESPONSIBILITY OF THE OWNER.
- 4. SEE SERVICE CONNECTION DETAIL FOR INFORMATION REGARDING MATERIALS.
- 5. SHOULD ANY SITUATION ARISE OTHER THAN SHOWN CONCERNING THE DEPTH OR OBSTRUCTION OF SERVICE LINE OR THE PLACEMENT OF METER PIT OR CURB BOX, CALL THE AUTHORITY IMMEDIATELY FOR DIRECTION.
- 6. THE CONTRACTOR IS RESPONSIBLE FOR NOTIFYING THE AUTHORITY AND THE TOWNSHIP PLUMBING DEPARTMENT FOR INSPECTION AT LEAST 48 HOURS IN ADVANCE OF THE WORK BEING PERFORMED.
- 7. IF THE INSPECTOR FOR THE AUTHORITY IS NOT PRESENT AT THE TIME OF THE INSTALLATION, THE TRENCH MUST REMAIN OPEN UNTIL THE SERVICE LINE IS INSPECTED BY AN AUTHORIZED REPRESENTATIVE OF THE AUTHORITY. NO TRENCH SHALL REMAIN OPEN OVERNIGHT.
- 8. CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL PERMITS.
- 9. SERVICE LINE MUST BE A MINIMUM OF 1" DIAMETER OF TYPE "K" COPPER FROM THE WATER MAIN TO THE PROPERTY LINE.

REVISED 10-08-03 CADD DRAWING BY GTS CONSULTANTS, INC.

DATE: JAN. 1991 DRAWN: G.G.&J.T.R. SCALE: NONE